

**Modifications in PreDCR:**

<b>New Layers Added</b>
_AutoFireAlarm
_AutoSprinkler
_CantileverParking
_DownComer
_DriveWay
_DryRiser
_Ent.Lobby
_FireExtinguisher
_HoseReel
_ManualFireAlarm
_ServiceSlab
_SmokeVent
_WetRiser
_YardHydrant

<b>Layer name changed</b>
_Balcony_Deck

<b>Markings Added</b>	
Floor in section	Flat slab
Lift	Fireman lift
	Stretcher Lift
Ramp	One Way for Car
	One Way for Scooter
	One Way for Transport
	Two Way for Car
	Two Way for Scooter
	Two Way for Transport
	Mid Landing
Driveway	One Way for Car
	One Way for Scooter
	One Way for Transport
	Two Way for Car
	Two Way for Scooter
Passage	Two Way for Transport
Passage	Car Lift Lobby

Parking	SUV Parking
	Rotary Parking
	Handed Over to Corporation
	Inline Parking
	Vertical Parking
Ancillary Structure	Receiving Station
	Descending Device
	Ascending Device
	Manhole
	Chamber
Tree	To be Removed
Service Duct	Electric Duct
	Fire Duct

<b>Marking Label changed</b>	
Lift	Car/Hoist Lift

<b>Insertion option Added</b>	
Parking	Differently Able
Driveway Direction arrows	Arrow 1
	Arrow 2

<b>Assign Name Added</b>	
Room	Green Room
	Convenience Shop

<b>Verification</b>
individual Parking is not allowed intersected or inside Manhole, septic tank, sewage treatment plant (Ancillary structure) Tank and Recreational Open space